



NOTES:

- 1) CARRIER PIPE SHALL BE PRESSURE TESTED PRIOR TO SEALING CASING
- 2) STEEL CASING AND CARRIER PIPE SHALL INCLUDE AN ANODE PER NMWD STD. NO.12 (USE ONE TERMINAL BOX FOR ALL TEST LEADS)

MINIMUM SIZE CASTING REQUIRED

PIPE SIZE	6"	8"	12"	14"	16"
CASING SIZE O.D.	16"	16"	20"	24"	30"
CASING WALL	.375	.375	.375	.375	.500
SKIDS	4	4	4	6	6

PARTS LIST:

1	INSULATOR, CALPICO INC. MODEL M-12 OR EQUAL
2	WRAP AROUND END SEALS, CALPICO INC. MODEL-W OR EQUAL

NORTH MARIN WATER DISTRICT
NOVATO, CALIFORNIA

WATERLINE INSTALLATION THROUGH CASING

APPROVED	DATE	REV.	STD. NO.
	5\16\02	1	8